

UNIVERSITY OF NEW HAMPSHIRE  
CONSTRUCTION AND RENOVATION STANDARDS

SECTION 09650 - RESILIENT FLOORING

PART 2 - PRODUCTS

1. Vinyl composition floor tile shall be used. Sheet vinyl flooring is not acceptable.
2. Provide replacement tiles - one box per 50 boxes or less installed of each color used. Replacement tiles shall be deposited with Clerk of Works before laying tiles.
3. Resilient floor tile shall be:
  - Kentile or Armstrong
  - 75% in "C" range
  - 25% in "D" range

PART 3 - EXECUTION

1. The floor shall be scrubbed and refinished with University approved finish/wax as part of the installation. Floor cleaning/finishing may be sub-contracted to UNH Housekeeping Services.
2. Resilient tile floors shall be protected, by the use of heavy paper, from all traffic at all times. It is preferred that tile work be scheduled for installation after other trades are complete.

END OF SECTION