

UNIVERSITY OF NEW HAMPSHIRE
CONSTRUCTION AND RENOVATION STANDARDS

SECTION 15500 - FIRE PROTECTION

PART 1 - GENERAL

1. All new installations and retrofits shall be inspected by the current UNH Sprinkler System Inspection Contractor during the warrantee period to verify compliance with NFPA Standard No.13.
2. At the completion of the project and/or final acceptance testing of the sprinkler system a copy of the Contractor's Certificate showing how the system functioned during the trip test and verifying that the air loss is less than one/half per pound day shall be supplied.

PART 2 - PRODUCTS

1. Dry Systems - A threaded piping system shall be used and there shall be less than a one/half pound air loss per day. A victolic system would only be used with the **prior written approval** of UNH Facilities Design and Construction.

PART 3 - EXECUTION

1. All drains and test connections for new installations shall be piped to allow **full flow**.

END OF SECTION